

# Fiber install guidelines

In order to avoid problems with fiber install quality, the following guidelines should be followed:

- Boxes should be located near floor or with long enough winder boxes to enable work on the floor.
  - No ladders should be necessary for maintenance/splicing.
- Cable should not be jammed in distribution boxes.
- All cables/ports should be labeled.
- All work should be centrally documented (Mesh or contractors).
- All fibers in a cable should be terminated initially. Never leave fibers unterminated.

---

Revision #10

Created 6 April 2023 18:24:54 by Guest

Updated 13 July 2024 20:18:42 by Guest